

At Your Service Heating and Cooling

Will perform the following procedures on all

AIR CONDITIONING with GAS HEAT M.A.-PTUS

1. Cycle the complete system (air conditioning and heating, as well as fan operation).
2. Replace up to one standard 1” throwaway filter, or clean one permanent filter per system.
3. Remove & clean the indoor blower assembly which includes the blower wheel on the indoor unit.
4. Remove and clean the indoor blower motor on the indoor unit.
5. Remove any trash and debris from indoor and outdoor units.
6. Lubricate all moving parts on indoor and outdoor units.
7. Test and record all voltages on indoor blower motor.
8. Test and record all amperages on indoor blower motor.
9. Test and examine all controls on indoor and outdoor units.
10. Tighten or adjust all belts and pulleys within indoor or outdoor units.
11. Examine and tighten all electrical connections on the indoor and outdoor units.
12. Examine and clean indoor evaporator coil (if accessible).
13. Clean and treat condensate drain line from indoor coil to main drain line (only to wall or floor).
14. Clean and treat condensate pump if part of the cooling drain system.
15. Clean and apply protective coating to indoor and outdoor cabinets.
16. Clean and adjust burner assembly.
17. Tighten and clean ignition assembly.
18. Clean heat exchanger and examine for possible cracks.
19. Test and record gas pressures at indoor furnace.
20. Leak test for gas leaks at furnace gas piping connections.
21. Monitor flue draft on gas furnace.
22. Test and record indoor air temperature.
23. Test and record indoor temperature drop in cooling mode.
24. Test and record indoor temperature rise in heating mode.
25. Test and record refrigerant pressures (low and high side).
26. Monitor refrigerant charge on refrigerant system.
27. Test and record superheat on refrigerant system.
28. Test and record sub-cooling on refrigerant system.
29. Clean outdoor condenser coil on outdoor unit.
30. Test and clean outdoor fan unit.
31. Test and record all voltages on outdoor unit (fan motor and compressor).
32. Test and record all amperages on outdoor unit (fan motor and compressor).
33. Visually inspect indoor and outdoor coils and copper tubing for refrigerant leaks.
34. Examine and tighten all electrical connections on disconnect of outdoor unit.